BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE
Office of Executive Engineer
SCHEDULE -B

Name Of Work :Additional works at Dry waste conter Abbigere and other works in ward no 12 Shettyhalli

Sub Division

Sl.No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2018-19, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work..	Cum	129.40	211.00	
2	Plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scafofolding and centering complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Cum	19.20	5421.00	
3	Providing laying palin / reinforced cement concrete for side Drain using M20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., completet excluding cost of steel ae per MMORTH specification No 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Cum	38.11	7070.00	
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Tonne	2.55	72316.00	

D.V

Scanned by CamScanner

5	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Sqm	257.40	1920.00	
6	Providing and laying Pre Cast Drain Cover slabs of 250mm thick for drain in cement concrete m 20 using graded ganite jelly 20 mm and down size with steel reinforcement, including form work, lift charges, curing and concrte finished surfaces on both side etc complete and as per drawing and directions of Engineer-in- charge of work	Sqm	21.00	5200.00	

D.V

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner